

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

THEM Engineering

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC The Brooklyn Bridge

AND/OR COMMON

The Brooklyn Bridge

2 LOCATION

STREET & NUMBER Over the East River, from Park Row (Manhattan) to
Adams Street (Brooklyn)

CITY, TOWN

New York

— VICINITY OF

— NOT FOR PUBLICATION

CONGRESSIONAL DISTRICT

19th

STATE

New York

CODE

36

COUNTY

New York

CODE

061

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input checked="" type="checkbox"/> PUBLIC	<input type="checkbox"/> OCCUPIED(not applicable)	<input type="checkbox"/> AGRICULTURE
<input type="checkbox"/> BUILDING(S)	<input type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL
<input checked="" type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY
			<input checked="" type="checkbox"/> TRANSPORTATION
			<input type="checkbox"/> OTHER:

4 OWNER OF PROPERTY

NAME The City of New York: The Hon. Michael Lazar, Administrator,
Transportation Administration (Department of Highways)

STREET & NUMBER

40 Worth Street

CITY, TOWN

New York

— VICINITY OF

STATE

New York

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, New York City Hall of Records
REGISTRY OF DEEDS, ETC.

STREET & NUMBER

31 Chambers Street

CITY, TOWN

New York

STATE

New York

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

— FEDERAL — STATE — COUNTY — LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION

___EXCELLENT
XGOOD
___FAIR

___DETERIORATED
___RUINS
___UNEXPOSED

CHECK ONE

___UNALTERED
XALTERED

CHECK ONE

XORIGINAL SITE
___MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Specifications alone reveal the impressive scale of the Brooklyn Bridge. Measuring 5,989' in length, it has a central, or river, span of 1,595'6" and two land spans of 930' each; the approach from the Brooklyn side is 971' while that from the New York side is 1,562'6". The bridge deck is suspended from four steel cables, each measuring 15 3/4" in diameter and 3,578'6" in length. Each cable consists of 5,434 individual wires with a total length of 3,515 miles, and is protected by 243 miles 943' of wire wrapping. The cables weigh 1,732,086 pounds apiece. The structure's two massive masonry towers stand 276'6" above high water, measuring 140' in length and 59' in width at the high water line and 136' x 53' at the top. There are, in all, 38,214 cubic yards of masonry in the Brooklyn tower and 46,945 cubic yards in the New York tower. The anchorages at either end of the bridge, in which are buried iron bars to which the cables are attached, each measure 129' x 119' at the base and 117' x 104' at the top and weigh 60,000 tons, or 120,000,000 pounds, apiece.

Among the bridge's most impressive elements are the caissons upon which the huge towers rest. Envisioned by John Roebling and built according to the design of Washington Roebling, the caissons resembled at the time of their construction mammoth boxes with V-shaped sides and no bottoms. Filled with compressed air in order to keep the river out and to prevent the structure itself from collapsing inward, each caisson was like a large room below the surface of the water that sank slowly toward the rock bottom of the East River as workmen inside removed foot after foot of the mud and stone of the river bed. The caisson supporting the Brooklyn tower was built first. It measured 168' x 102' and had an over-all height of 14 1/2', which included a 5 foot thick roof of solid timber (to which were later added ten more courses of timber, giving the caisson a total height of 21'6"). Its roof was penetrated by two air locks, two supply shafts, and two water shafts through which clamshell scoops removed the earth and stone dug up by the workmen. The sides of the caisson tapered from 9' in thickness at the top to 8" at the bottom. This bottom cutting edge, or "shoe," was shod with a heavy iron casting and was sheathed with boiler plate. The entire caisson was wrapped with a layer of tin and then sheathed with more wood. The interior of the Brooklyn caisson was divided by partitions, which acted as additional supports, into six chambers, and had a total bearing surface of 1,050 lineal feet, a factor to be reckoned with when faced with the surprising size of the boulders encountered along the structure's downward journey. Constructed at Webb & Bell, shipyards, Greenpoint, the caisson weighed 3,000 tons when it was launched on March 19, 1870. It was towed into position on May 3rd and 4th, lowered shortly thereafter, and was placed in operation on May 21st. Impeded by an unexpectedly large number of boulders, some of which measured up to 14' in length and 5' in diameter, and set back 2-3 months by a fire which caused considerable damage to the timber roof, the caisson was finally filled with concrete on March 11, 1871, resting at a depth of 44'6" below high water. As an indication of the care and foresight with which Roebling designed and built the caisson, the structure was once subjected to a total weight of 23 tons per square foot--as compared to the 5 ton total it would be required to hold after the tower was built--

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input checked="" type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input checked="" type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION			

SPECIFIC DATES 1869-1883

BUILDER/ARCHITECT John A. Roebling
Washington A. Roebling

STATEMENT OF SIGNIFICANCE

A national symbol and a world-renowned landmark, the Brooklyn Bridge will celebrate its 92nd birthday this year. Designed by John A. Roebling, who came to America from Prussia in 1831, and built under the careful scrutiny of his son and successor, Colonel Washington A. Roebling, the bridge was for twenty years the largest suspension bridge in the world. In addition, the building of the bridge required a variety of new and unusual construction techniques, among them, the use of pneumatic caissons and the use of steel--instead of iron--cable. A majestic and impressive structure, little altered from its original form, the bridge stands today as a testament to the vision and determination of both its designers and its builders.

In many ways, the bridge is the crowning symbol of an age fraught with engineering accomplishments. Perhaps only the building of the nation's first transcontinental railroad and the erecting of the Eads bridge across the Mississippi River at St. Louis can be compared to the magnitude of the project undertaken by the Roeblings. As John Roebling himself wrote in 1867:

The completed work, when constructed in accordance with my designs, will not only be the greatest bridge in existence, but will be the greatest engineering work of the continent, and of the age. Its most conspicuous features, the great towers, will serve as landmarks to the adjoining cities, and they will be entitled to be ranked as national monuments. As a great work of art, and as a successful specimen of advanced bridge engineering, this structure will forever testify to the energy, enterprise and wealth of that community which shall secure its erection.

The bridge also stands as the ultimate expression of the art practiced by the Roeblings. John Roebling was responsible for suspension bridges over the Monongahela River at Pittsburgh (1846), over the Delaware River near Port Jervis, New York (1848), over the gorge of the Niagara River near the famous Falls (1855), over the Allegheny River at Pittsburgh (1860), and over the Ohio River at Cincinnati (1867), a project in which Colonel Roebling greatly assisted his father in the capacity of Assistant Chief Engineer. The Brooklyn Bridge represents the culmination of their collective skills. A final and supreme endeavor, it was indirectly responsible for the senior Roebling's death in July, 1869, and directly

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Condit, Carl W., American Building Art, New York, 1961.

McCullough, David, The Great Bridge (New York, 1972).

Plowden, David, Bridges (New York, 1974).

Steinman, David B., The Builders of the Bridge, New York, 1950.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY c. 20

UTM REFERENCES

A

1	8
---	---

5	8	5	3	5	0
---	---	---	---	---	---

4	5	0	5	8	0	0
---	---	---	---	---	---	---

B

1	8
---	---

5	8	5	3	1	0
---	---	---	---	---	---

4	5	0	5	7	7	0
---	---	---	---	---	---	---

C

1	8
---	---

5	8	4	0	6	0
---	---	---	---	---	---

4	5	0	7	0	4	0
---	---	---	---	---	---	---

D

1	8
---	---

5	8	4	1	1	0
---	---	---	---	---	---

4	5	0	7	0	7	0
---	---	---	---	---	---	---

VERBAL BOUNDARY DESCRIPTION

The boundaries are formed by the extremities of the bridge itself--i.e., the end of the approach on the New York side and the end of the approach on the Brooklyn side, a total of 5,989', and by the width of the tower piers, about 150 feet.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
New York	36	New York	061

STATE	CODE	COUNTY	CODE
New York	36	Kings	047

11 FORM PREPARED BY

NAME / TITLE

James B. Armstrong, original form prepared by S. Sydney Bradford, HSS, 1963

ORGANIZATION

Historic American Engineering Record

DATE

Feb. 24, 1975

STREET & NUMBER

Department of the Interior, National Park Service

TELEPHONE

202-523-5460

CITY OR TOWN

Washington

STATE

D.C.

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL ____

STATE ____

LOCAL ____

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

FEDERAL REPRESENTATIVE SIGNATURE

TITLE

DATE

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

DATE

DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION
ATTEST:

DATE

KEEPER OF THE NATIONAL REGISTER

(NATIONAL HISTORIC
LANDMARKS)

(NATIONAL HISTORIC
LANDMARKS)

(NATIONAL HISTORIC
LANDMARKS)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7

PAGE 2

yet sustained little damage and lost none of its airtightness.

The New York caisson, which was launched on May 8, 1871 and towed into position on September 11th, outweighed its predecessor by 250 tons and measured an additional four feet in length. Having seven more courses of timber on its roof, it was considerably taller than the Brooklyn caisson, measuring 31'6" when completed. Other changes in design included the addition of 50 iron pipes 4" in diameter for the removal of sand from the river bed, and a lining of thin boiler plate as a protection against fire and as a further means of achieving airtightness. Whereas workmen on the Brooklyn side experienced slow progress as a result of a rocky bottom, those on the New York side were faced with a faster, but considerably deeper, descent. As a result, they became susceptible to what is known as the caisson disease, or the bends, a debilitating, often crippling, and sometimes even fatal malady. Between January 25 and May 31, 1872, 110 cases of the disease were reported by Dr. Andrew H. Smith, the official physician, with a great number undoubtedly escaping his attention. On May 18th, after a third worker died, Roebling called a halt to the work within the caisson, believing that where it rested, 78'6" below high water, the sand and gravel were so tightly compacted that the bedrock itself could not provide a stronger foundation. Accordingly, the caisson was filled with stone, earth, sand, and concrete, a job that was completed on July 12th.

The towers erected upon these man-made foundations are built of limestone and granite from quarries located as far away as Maine. Their gothic arches, with openings 33'9" wide, rise 117' above the roadway. By no means as complex as the building and sinking of the caissons, the construction of the towers was nonetheless a demanding affair. While the distance between the top of the tower and the ground was relatively small, large derrick booms mounted atop the tower were used to hoist up the blocks of granite. When this distance became too great, a complex lifting system, involving iron pulleys and a steel wire rope 1 1/2" in diameter run by a steam engine on the ground, was employed. Once the blocks had been hauled up, dragged along a timber track running up one side of the tower, they were lifted into place by a boom derrick stationed on top. It was slow, exacting work--the keystones of the arches of the Brooklyn tower, for example, weigh 11 tons apiece. The towers each required some four years to complete, the Brooklyn tower being finished in June 1875 and the New York tower thirteen months later.

In contrast to the towers, the anchorages are built almost entirely of limestone. Buried deep within each of them are four oval anchor plates that measure 16' x 17 1/2' and are 2 1/2' thick. Each weighs 23 tons, or 46,000 pounds. From every anchor plate 18 wrought iron eyebars spring in a double-tiered chain. This chain describes an arc, rising through more than 80' of masonry, surfacing approximately 25' back from the edge of the anchorage

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 3

that faces the tower. The bars that compose the chain average 12 1/2' in length and measure up to 9" x 3" in thickness, and are joined together by large metal pins. The Brooklyn anchorage, which was begun in February 1873, was completed in November 1875 while the New York anchorage required less time to be built, being constructed between May 1875 and July 1876.

Among the most complex and innovative processes used in the building of the bridge was the spinning of the gigantic steel cables. To begin with, a series of wires of increasing thickness was strung between the two anchorages, over the two towers. The smallest wire was used to pull a slightly larger one across, which, in turn, was used to pull an even larger one, and so on. Once a rope 2 1/4" in diameter had been strung, workmen suspended five cradles, or platforms, one between each anchorage and tower, and three between the two towers. From them the workmen were able to guide and inspect the almost innumerable wires of crucible steel that eventually comprised the 19 strands that made up each of the large cables. Since the individual wires were delivered in lengths of only a few hundred feet, galvanized steel ferrules 2" long were used for splicing. The wires were strung by means of a "carrier," a large iron wheel fastened to the working rope by a bent iron arm. There were two carriers, each moving in an opposite direction to the other. Thus, as one traveled across the river with a loop of wire--thereby stringing two wires at once--the other moved toward the anchorage just vacated by its partner. All the wire was strung from the Brooklyn side so that the carrier returning from New York was always empty. In all, 5,434 individual steel wires were strung, 152 more than Roebling had initially envisioned. The extra wires were added to combat the weakness of some 221 tons of wire that were determined to be deficient after they had been laid up. Even with the unsound wire, however, the cables were still figured to have a safety margin of five, that is, they were capable of supporting five times the weight they would normally bear. Each cable was rated as having an ultimate strength of 24,621,780 pounds. From the cables hundreds of steel suspenders were hung to the deck of the bridge. There are 208 of these wire rope suspenders between each cable and the river span, and 86 between each cable and each land span. At the time of the bridge's opening, each suspender was rated as having a strength of 70 tons. In addition, inclined, or diagonal, stays were strung between the tops of the towers and numerous points along the deck. These stays, which were designed to increase the bridge's rigidity, were strong enough by themselves to hold up 15,000 tons, more than the weight of the entire deck.

The bridge was designed to be used by pedestrians, vehicles, and cable cars. Accordingly, an elevated promenade was constructed down the center of the 85' wide roadway, which rises from a height of 119' above high water at each tower to a height of 135' at the center of the river span. Beneath the

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 4

walkway, to either side of the crossframe that helps support it, ran specially designed cable cars, which by 1888 were carrying more than 30,000,000 passengers a year. The remainder of the roadway was used by vehicular traffic, with two lanes on either side of the cable car tracks. Later, trolleys were added, and after them, elevated subway trains, or "els." The els were discontinued in 1944, at which time the iron terminal buildings at either end of the bridge were dismantled. Starting in 1948, a major upgrading of the bridge took place. The tracks were torn up and the roadway widened to three lanes on either side, and additional trusswork was built. Although \$9,000,000 was spent, changes to the bridge's general appearance were minimal.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 2

responsible for the younger Roebling's virtual incapacitation.

The bridge continues to serve Brooklyn and New York efficiently, carrying more than 121,000 trucks and cars every day. In addition, hundreds of pedestrians still use its elevated walkway on weekends. That the bridge required almost a decade and a half of steady, demanding work attests to the enormity of the project undertaken by the Roeblings; that it has functioned smoothly for more than ninety years is proof of the soundness of their abilities.